




Introduction

1. **AVOID** the tree and its root systems in the first place.
2. **MINIMISE** damage via consultation with Parks & Open Space department if the tree root zone and construction zone overlap or are in close proximity with each other.
3. **OFFSET** the loss of tree as a last resort if approval has been given. In regards to tree replacement, parity of vegetation in the landscape is essential.



Key Objectives

- Describe the importance of trees in the landscape
- Describe how trees can be adversely impacted by construction works
- Outline tree protection measures and a process to ensure these are implemented from the planning to post-construction phases of projects.

- **Importance of retaining trees in the landscape**
- Introduction to trees and their root systems
- Ideal tree protection workflow
- Method of protection
- Maintenance of TPZ during construction
- Recommended monitoring and certification process



Trees are important community assets



Category	Particular benefit of street trees
Climate amelioration	<ul style="list-style-type: none"> Shade & Temperature modification Humidifying the air Shelter from the wind Reduced runoff
Human health	<ul style="list-style-type: none"> Lower peak summer air temperatures Encourage active forms of transport – walking and cycling Human psychological health
Landscape values	<ul style="list-style-type: none"> A sense of scale Softening of the built landscape Linking and unifying landscapes Variety of colour, form, texture and pattern
Environmental values and amelioration	<ul style="list-style-type: none"> Protecting waterways Links to areas of natural significance (waterways, parklands) Fixing of carbon dioxide & Production of oxygen Purifying the air
Conservation values	<ul style="list-style-type: none"> Maintain wildlife habitat & Conserve genetic resources
Economic benefits	<ul style="list-style-type: none"> Increased property values Increased shopping activity Carbon balance benefits



- Importance of retaining trees in the landscape
- Introduction to trees and their root systems
- Ideal tree protection workflow
- Method of protection
- Maintenance of TPZ during construction
- Recommended monitoring and certification process





- Importance of retaining trees in the landscape
- Introduction to trees and their root systems
- **Ideal tree protection workflow**
- Method of protection
- Maintenance of TPZ during construction
- Recommended monitoring and certification process




Table 1: Indicative stages in development and the tree management process.

Stage in development	Tree management process	Arborist actions and certification
Planning		
Site acquisition	Legal constraints	
Detail surveys	Council plans and policies	Existing trees accurately plotted on survey plan (this is a critical requirement that sets the foundation for the whole process)
	Planning instruments and controls	
Preliminary tree assessment	Heritage	Evaluate trees suitable for retention and mark on plan
	Threatened species	
Preliminary development design	Hazard/risks	Provide preliminary arboricultural report and indicative TPZs to guide development layout
	Tree retention value	
Development submission	Condition of trees	Planning selection of trees for retention
	Proximity to buildings	
Development approval	Location of services	Design review by proponent
	Roads	
	Level changes	Design modifications to minimize impact to trees
	Building operations space	
	Long-term management	
	Identify trees for retention through comprehensive arboricultural impact assessment of proposed construction.	Provide arboricultural impact assessment including tree protection plan (drawing) and specification
	Determine tree protection measures	
	Landscape design	
	Development controls	Review consent conditions relating to trees
	Conditions of consent	

AS 4970-2009

Pre-construction		
Initial site preparation	State based OHS requirements for tree work Approved retention/removal Refer to AS 4373-2007 for the requirements on the pruning of amenity trees Specifications for tree protection measures	Compliance with conditions of consent Tree removal/tree retention/transplanting Tree pruning Certification of tree removal and pruning Establish/delineate TPZ Install protective measures Certification of tree protection measures
Construction		
Site establishment	Temporary infrastructure Demolition, bulk earthworks, hydrology	Locate temporary infrastructure to minimize impact on retained trees Maintain protective measures Certification of tree protection measures
Construction work	Liaison with site manager, compliance Deviation from approved plan	Maintain or amend protective measures Supervision and monitoring
Implement hard and soft landscape works	Installation of irrigation services Control of compaction work Installation of pavement and retaining walls	Remove selected protective measures as necessary Remedial tree works Supervision and monitoring
Practical completion	Tree vigour and structure	Remove all remaining tree protection measures Certification of tree protection
Post construction		
Defects liability/maintenance period	Tree vigour and structure	Maintenance and monitoring Final remedial tree works Final certification of tree condition

AS 4970-2009

- Importance of retaining trees in the landscape
- Introduction to trees and their root systems
- **Ideal tree protection workflow**
- **Method of protection**
- Maintenance of TPZ during construction
- Recommended monitoring and certification process

Tree Protection Zone

- Depends on the type of tree
- Whenever staff or contractors are in doubt if the planning scheme provisions apply, they need to contact Council's Environmental Planner.


Tree type	TPZ calculation	Minimum or maximum values
Remnant trees	2 x crown width	Min 2m No maximum value
Palms, other monocots, cycads and tree ferns (AS 4970)	Edge of crown + 1m	
All other trees (AS 4970)	12 x DBH (radius)	Min 2m Max 15m (unless inadequate for crown protection)



Remnant Trees

Protected under a Native Vegetation Precinct Plan or Offset Management Plan

TPZ = 2 x crown width
(no maximum value)



Palms, cycads and tree ferns

TPZ not less than 1m outside the crown protection (AS 4970)

All other trees



Tree Protection Zone



NO ACCESS


Contact:







Image courtesy of Chris Lawry




- built structures or hard landscape features (i.e. paving, retaining walls)
- materials storage (i.e. equipment, fuel, building waste or rubble)
- soil disturbance (i.e. stripping, grade changes, placement of fill)
- excavation works including soil cultivation (specifically surface-dug trenches for underground utilities)
- lighting of fires
- preparation of chemicals, including cement products and cleaning of any vehicles or plant
- vehicular or pedestrian access (i.e. pathways or parking of vehicles or plant).

Encroachment into the TPZ

Level of encroachment	Definition	Requirement
Minor	Less than 10% of the TPZ area Outside the SRZ	Area compensated for by an offset area adjoining the TPZ
Major	Greater than 10% of the TPZ area Within the SRZ	Arborist must demonstrate that the tree will remain viable Non-destructive root investigation may be required



Image courtesy of Chris Lawry



- Importance of retaining trees in the landscape
- Introduction to trees and their root systems
- Ideal tree protection workflow
- Method of protection
- Maintenance of TPZ during construction
- Recommended monitoring and certification process

- ### Maintenance of TPZ
- Fencing is secure and located at the edge of the TPZ
 - Mulch 50-100mm
 - Weed removal
 - Watering



Image courtesy of Chris Lawry

- Importance of retaining trees in the landscape
- Introduction to trees and their root systems
- Ideal tree protection workflow
- Method of protection
- Maintenance of TPZ during construction
- Recommended monitoring and certification process

Tree protection activity	Purpose	Arborist to certify or monitor	Comment
Tree Protection Plan	Identifies key stages where monitoring and certification will be required	Certify plan	The arborist to meet with site manager and contractors to discuss Tree Protection Plan TPZs should be shown on all relevant construction plans
Tree removal and pruning		Confirm correct trees are marked for removal. Certify the works on completion	Undertaken prior to TPZ fencing being erected Engage qualified practical arborists. Tree pruning as per AS 4373.
TPZ fencing installation and inspections	Provide physical protection to the trees	Certify the TPZ fencing and other protection measures	Install protection measures as per Tree Protection Plan
Site establishment and construction		Monitor any demolition, earthworks or construction within the TPZ	Discuss construction management plan with project arborist. Notify project arborist prior to works
Landscaping		Monitor any hard landscaping works within the TPZ	
Practical completion		Assess tree condition and certify practical completion	
Post construction		Assess tree condition	

- ### Conclusion
- Trees are important community assets and require protection
 - Avoid, minimise, offset
 - Tree root systems are typically shallow
 - Set up a Tree Protection Zone
 - Arborists should be involved from the planning to post-construction phase to ensure trees are protected

